

Dorchester Road, Wool

Overview:

Site Location:	>> Wool
Client:	>> Wessex Water
Contract Value:	>>
Project Duration:	>> 9 weeks



Auger boring process



Accommodation works necessary

The works comprise the construction of a new 270m of 450mm diameter gravity sewer by using auger boring techniques and the construction of six manholes. B & W carried out the auger boring works.

The 9 week programme required completion by 31st March 2008. The turning of the flows was achieved by the March deadline, however due to additional instructed works there was a 3 week overrun to complete the works including reinstatement. The scheme was very onerous but working with the Client as a team ensured a successful outcome.



The Client for the scheme is
Wessex Water Services Ltd



Landscaping works along the route



Lewis Civil Engineering Ltd, Mwyndy Cross Industries, Cardiff Road, Pontyclun, Rhondda Cynon Taff. CF72 8PN

Telephone: 01443 449 200 Fax: 01443 449 201

Website: www.lewis-ltd.co.uk E-mail: enquiries@lewis-ltd.co.uk